



NOTE: WRAP THERMOSTAT PROB TO SECURE IN PLACE.

NOTE: CUT AROUND INTAKE DUCTS HOLES

NOTE: DRILL INTO WATER DRAIN PAN TO SECURE IN PLACE. BOTH SIDES.

ITEM	QTY	U/M	PART NUMBER	DESCRIPTION
35	1	EACH	VAL00000	VALVE, TX, BLOCK TYPE, 1.5 TON, R-134A
34	34	EACH	STSO3050	SCREW, TH, PD, 10-32x .50, ST, PLT
33	4	EACH	SCP03079	SCREW, PH, SD, 8-32 X .75, 18.8, SS
32	12	EACH	SCP03075	SCREW, PH, SDT, #10-16 x .75, ST, PLT
31	34	EACH	NTS03001	NUT, RIV, 10-32 UNF
30	4	EACH	NTL03001	NUT, LOCK, HEX, NYLON, 8-32, 18.8, SS
29	1	EACH	M3219	STRAIGHT-THRU, LIQUID TIGHT, FITTING
22	1	EACH	FOA10312	FOAM, INSULATION, 1", FRT, R-5, '14
21	1	EACH	FOA10311	FOAM, INSULATION, 1", TOP, R-5, '14
20	1	EACH	FOA10310	FOAM, INSULATION, 1", BOTTOM, R-5, '14
19	1	EACH	FOA10309	FOAM, INSULATION, 1", REAR, R-5, '14
18	1	EACH	FOA10308	FOAM, INSULATION, 1", R/S, R-5, '14
17	1	EACH	FOA10307	FOAM, INSULATION, 1", L/S, R-5, '14
16	1	EACH	FOA05914	FOAM, ANTI-SPLA, 15PPI, .5" x13.75" x 16.625"
15	2	EACH	FOA01816	FOAM, ANTI-SWT, 1/8" x 8.5" x 16.5"
14	2	EACH	FOA01814	FOAM, ANTI-SWT, 1/8" x 8.5" x 14"
13	1	EACH	EVC30001	D3RE/FE EVAP COIL
12	1	EACH	EBX15054	BKT, WELDMT, GRILL, RETURN AIR, HDX, '15
11	1	EACH	EBX15049	EVAP, COVER, PASSTHRU, FITTING, '14
10	1	EACH	EBX15048	EVAP, MAIN, BOX, WELDMT, '14
9	1	EACH	EBX15046	EVAP, BLOWER, OUTLET, PANEL, '14
8	1	EACH	EBX15045	EVAP, COVER, TOP, '14
7	1	EACH	EBX15044	EVAP, COVER, FRONT, TX VALVE, '14
6	1	EACH	EBX15041	EVAP, PAN, DRAIN, WELDMT, '14
5	1	EACH	EBX15038	BKT, SUPPORT, LID, HXC, '12
4	5	EACH	CLP36001	CLAMP, GEAR, #36, 1 13/16-2 3/4, (46/70mm)
3	1	EACH	BLO00005	BLOWER, 12 V, 510 m3HR (300 CFM)
1	1	EACH	T2-00685-00	THERMOSTAT, FREEZE-UP, NON-ADJ., G5

TRANSARGTIC INC.

1	ADDED P/N# EBX15054	8/1/2015	JRR	9/18/2014
0	RELEASED TO PRODUCTION	8/18/2014	JRR	GA
REV	DESCRIPTION	DATE	BY	
1		9/18/2014	James Stewart	
2		9/18/2014	Ron Norborck	
3		9/18/2014	Dale Mason	

UNSPECIFIED TOLERANCES: HOLE ±.001
 ONE DECIMAL PLACE (X) .001
 TWO DECIMAL PLACE (XX) .0005
 THREE DECIMAL PLACE (XXX) .0002
 FRACTIONAL (1/16") ANGULAR ±.25°



DRAWN	rrcoelen	9/18/2014	TITLE	KIT, INSTALL, UNDERFLOOR, 400 CFM, '14
CHECKED	Val Jakowlew	9/18/2014	SIZE	D
APPROVED	Ron Norborck	9/18/2014	DWG NO	KDA00090
DATE	Dale Mason	9/18/2014	SCALE	1:1
DRAWING UNIT OF MEASURE	MM (INCH)		SHEET	1 OF 1